

Contactor relay, 3N/0+1N/C, AC

Part no. DILA-31(24V50/60HZ)
Article no. 276368
Catalog No. XTRE10B31T



Delivery program

		DILA relays
		Contactor relays
		Basic devices with positive operation contacts
		Screw terminals
l _e	Α	4
I _e	Α	4
		3 N/O
		1 NC
		A1 1 1 2 1 3 3 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4
		31E
		DILA-XHI(V)
		24 V 50/60 Hz
		AC operation
		Contact numbers to EN 50011 Coil terminal markings to EN 50005

Technical data

General

General			
Standards			IEC/EN 60947, VDE 0660, UL, CSA
Lifespan, mechanical			
AC operated	Operations	x 10 ⁶	10
DC operated	Operations	x 10 ⁶	10
Maximum operating frequency		Ops./h	
Maximum operating frequency	Operations/h		9000
Climatic proofing			Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30
Ambient temperature			
Open		°C	-25 - +60
Enclosed		°C	- 25 - 40
Ambient temperature, storage		°C	- 40 - 80
Mounting position			
Mounting position			30°
Mechanical shock resistance (IEC/EN 60068-2-27)			
Half-sinusoidal shock, 10 ms			
Basic unit with auxiliary contact module		g	
N/O contact		g	7
N/C contact		g	5

Degree of Protection			IP20
Protection against direct contact when actuated from front (EN 50274)			Finger and back-of-hand proof
Weight			i niger and back-or-nand proof
AC operated		ka	0.23
DC operated		kg kg	0.28
Terminal capacities		mm ²	0.20
		mm	
Screw terminals			4 (0.75 4)
Solid		mm ²	1 x (0,75 - 4) 2 x (0,75 - 2,5)
Flexible with ferrule		mm ²	1 x (0.75 - 2.5) 2 x (0.75 - 2.5)
Solid or stranded		AWG	18 - 14
Terminal screw			M3.5
Pozidriv screwdriver		Size	2
Standard screwdriver		mm	0.8 x 5.5 1 x 6
Max. tightening torque		Nm	1.2
Spring-loaded terminals			
Solid		mm ²	1 x (0.75 - 2.5) 2 x (0.75 - 2.5)
Flexible with or without ferrule DIN 46228		mm^2	1 x (0,75 - 1.5) 2 x (0,75 - 1.5)
Solid or stranded		AWG	18 - 14
Standard screwdriver		mm	0.8 x 5.5
Contacts			1x6
Positive operating contacts to ZH 1/457, including auxiliary contact module			Yes
Rated impulse withstand voltage	U _{imp}	V AC	8000
Overvoltage category/pollution degree	p		III/3
Rated insulation voltage	U _i	V AC	690
Rated operational voltage	U _e	V AC	690
Rated operational current	- 6	A	
Conventional free air thermal current, 3 pole, 50 - 60 Hz		^	
Open			
Conv. thermal current	I _{th}	Α	16
AC-15	u.		
220 V 230 V 240 V	l _e	Α	4
380 V 400 V 415 V	I _e	Α	4
500 V	I _e	A	1.5
DC current	'e	^	
DC-13 L/R - 15 ms			
Contacts in series:		A	
1	24 V	A	10
1	60 V	A	6
2	60 V	A	10
1	110 V	A	3
3	110 V	Α	6
1	220 V	A	1
3	220 V	Α	5
$_{DC\ L/R} \leq _{50\ ms}$			
Contacts in series:		Α	
3	24 V	Α	4
3	60 V	Α	4
3	110 V	Α	2
3	220 V	Α	1
Conv. thermal current	I _{th}	Α	16

between coil and auxiliary contacts		V AC	400
between the auxiliary contacts		V AC	400
Control circuit reliability	Failure rate	λ	
Control of our Condesiney	Tunuro Tuto	,,	$<10^{-8}$, $<$ one failure at 100 million operations (at $U_e = 24 \text{ V DC}$, $U_{min} = 17 \text{ V}$, $I_{min} = 5.4 \text{ mA}$)
Short-circuit rating without welding			
Maximum overcurrent protective device			
220 V 230 V 240 V		PKZM0	4
380 V 400 V 415 V		PKZM0	4
Short-circuit protection maximum fuse			
500 V		A gG/gL	10
Current heat loss at I _{th}			
AC operated		W	0.3
DC operated		W	0.3
Magnet systems			
Voltage tolerance			
AC operated		$x\; U_{c}$	
	Pick-up	x U _c	0.8 - 1.1
DC operated		x U _c	
	Pick-up	x U _c	0.8 - 1.1
at 24 V: without auxiliary contact component (40 °C)	Pick-up	x U _c	0.7 - 1.3
Power consumption			
50 Hz	Pick-up	VA	24
50 Hz	Sealing	VA	3.4
50 Hz	Sealing	W	1.2
60 Hz	Pick-up	VA	30
60 Hz	Sealing	VA	4.4
60 Hz	Sealing	W	1.4
50/60 Hz	Pick-up	VA	27 25
50/60 Hz	Sealing	VA	4.2 3.3
50/60 Hz	Sealing	W	1.4 1.2
DC operated	Pull-in = sealing	W	3
duty factor		% DF	100
Changeover time at 100 % U_C (recommended value)			
AC operated closing delay		ms	15 - 21
AC operated N/O contact opening delay		ms	9 - 18
DC operated closing delay		ms	
Switching times, DC operated, max. closing delay		ms	31
DC operated N/O contact opening delay		ms	
Cuitabia atiana DC actuated male anatost On mine dalar mare			40

Notes

Notes Making and breaking conditions to DC-13, time constant as stated Smoothed DC, three-phase bridge rectifiers or smoothed double-wave rectification

Switching times, DC actuated make contact Opening delay, $\ensuremath{\mathsf{max}}$.

Design verification as per IEC/EN 61439

Technical data for design verification			
Rated operational current for specified heat dissipation	In	Α	15.5
Heat dissipation per pole, current-dependent	P _{vid}	W	0.5
Equipment heat dissipation, current-dependent	P _{vid}	W	0
Static heat dissipation, non-current-dependent	P_{vs}	W	1.4
Heat dissipation capacity	P _{diss}	W	0
Operating ambient temperature min.		°C	-25
Operating ambient temperature max.		°C	60
EC/EN 61439 design verification			

12


10.2 Strength of materials and parts	
10.2.2 Corrosion resistance	Meets the product standard's requirements.
10.2.3.1 Verification of thermal stability of enclosures	Meets the product standard's requirements.
10.2.3.2 Verification of resistance of insulating materials to normal heat	Meets the product standard's requirements.
10.2.3.3 Verification of resistance of insulating materials to abnormal heat and fire due to internal electric effects	Meets the product standard's requirements.
10.2.4 Resistance to ultra-violet (UV) radiation	Meets the product standard's requirements.
10.2.5 Lifting	Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 Mechanical impact	Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 Inscriptions	Meets the product standard's requirements.
10.3 Degree of protection of ASSEMBLIES	Does not apply, since the entire switchgear needs to be evaluated.
10.4 Clearances and creepage distances	Meets the product standard's requirements.
10.5 Protection against electric shock	Does not apply, since the entire switchgear needs to be evaluated.
10.6 Incorporation of switching devices and components	Does not apply, since the entire switchgear needs to be evaluated.
10.7 Internal electrical circuits and connections	Is the panel builder's responsibility.
10.8 Connections for external conductors	Is the panel builder's responsibility.
10.9 Insulation properties	
10.9.2 Power-frequency electric strength	Is the panel builder's responsibility.
10.9.3 Impulse withstand voltage	Is the panel builder's responsibility.
10.9.4 Testing of enclosures made of insulating material	Is the panel builder's responsibility.
10.10 Temperature rise	The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 Short-circuit rating	Is the panel builder's responsibility. The specifications for the switchgear mus observed.
10.12 Electromagnetic compatibility	Is the panel builder's responsibility. The specifications for the switchgear must observed.
10.13 Mechanical function	The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

Technical data ETIM 6.0


Low-voltage industrial components (EG000017) / Contactor relay (EC000196)			
Electric engineering, automation, process control engineering / Low-voltage switch technology / Contactor (LV) / Contactor relay (ecl@ss8.1-27-37-10-01 [AAB716011])			
Rated control supply voltage Us at AC 50HZ	V	24 - 24	
Rated control supply voltage Us at AC 60HZ	V	24 - 24	
Rated control supply voltage Us at DC	V	0 - 0	
Voltage type for actuating		AC	
Rated operation current le , 400 V	А	4	
Connection type auxiliary circuit		Screw connection	
Mounting method		DIN-rail/screw	
Interface		No	
Number of auxiliary contacts as normally closed contact		1	
Number of auxiliary contacts as normally open contact		3	
Number of auxiliary contacts as normally closed contact, delayed switching		0	
Number of auxiliary contacts as normally open contact, leading		0	
With LED indication		No	
Number of auxiliary contacts as change-over contact		0	
Manual operation possible		No	


Approvals

• •	
Product Standards	IEC/EN 60947-4-1; UL 508; CSA-C22.2 No. 14-05; CE marking
UL File No.	E29184
UL Category Control No.	NKCR
CSA File No.	012528
CSA Class No.	3211-03
North America Certification	UL listed, CSA certified
Specially designed for North America	No




1: Suppressor 2: Auxiliary contact module






Component lifespan (operations) le = Rated operational current

Dimensions





Additional product information (links)

The state of the s		
IL03407013Z (AWA2100-2126) Contactors		
IL03407013Z (AWA2100-2126) Contactors	ftp://ftp.moeller.net/DOCUMENTATION/AWA_INSTRUCTIONS/IL03407013Z2012_03.pdf	
UL/CSA: Approved rating data	http://de.ecat.moeller.net/flip-cat/?edition=HPLTE&startpage=5.84	